

# ADDENDUM 2

**To:** Prospective Bidders  
**From:** Matt Campbell, Project Manager  
**Subject:** Williamson County Schools- RFB #1206 Fairview HS Stormwater Improvements  
**Date:** April 21, 2020

Failure of any Bidder to receive this addendum shall not relieve such Bidder from any obligation under his bid as submitted.

## Changes:

See new bid sheets attached for all of Section 014 pages 23-28 attached. This will replace the original bid book pages 23-28. You will notice the Title of Page 23 listed now as:

### **(UPDATED) SECTION 014 ESTIMATED QUANTITIES (BID FORM).**

Item #1: Page 25- **Item # 709-05.13:** Machined Rip Rap (Surge Stone) 363 Tons- Added to address possible unsuitable subgrade material under new asphalt section.

Item #2: Page 25- **Item # 740-10.01:** Geotextile (Type 1) (Subsurface Drainage) 312 SY- Added to address possible unsuitable subgrade material under new asphalt section.

Item #3: Page 27- Note #4 was added: Any work required on the plan without a specific line item shown, should be included in the cost of other items.

Item #4: Page 27 (Contained in original bid book)- Add Alternate #1- Fairview H.S. Football Drainage and Erosion- **Williamson County Schools has canceled Add Alternate #1 for this project.** Bidders are not required to submit pricing.

We apologize for any inconvenience this has caused in getting your bids together. Please contact our office if you have any questions.

**(UPDATED) SECTION 014  
ESTIMATED QUANTITIES (BID FORM)**

**PROJECT: RFB #1206 FAIRVIEW HIGH SCHOOL STORMWATER IMPROVEMENTS**

The Bidder shall fill in a unit price and the total price for each item contained in this Proposal. Failure to fill in a unit price for any item will be considered sufficient grounds for declaring the bid irregular.

*Bid Formula: Estimated Quantity x Unit Price= Total*

**\*NOTE: IF BID EXCEEDS FUNDS AVAILABLE, WILLIAMSON COUNTY SCHOOLS RESERVES THE RIGHT TO REDUCE THE QUANTITY TO FIT AVAILABLE FUNDS. ALL ITEMS SHALL BE BID WITH THE UNDERSTANDING THAT THE QUANTITY FOR ANY ITEM MAY BE INCREASED, DECREASED, OR DELETED AT THE DIRECTION OF THE ENGINEER OR OWNER.**

**BASE BID**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>UNIT</b>	<b>ESTIMATED QUANTITY</b>	<b>UNIT PRICE</b>	<b>TOTAL</b>
105-01	CONSTRUCTION STAKES, LINES, AND GRADES <b>SEE NOTE 1</b>	L.S.	1.00		
202-01.50	REMOVAL OF STRUCTURES & OBSTRUCTIONS (INLETS/MANHOLES)	EACH	1.00		
202-01.51	REMOVAL OF STRUCTURES & OBSTRUCTIONS (HEADWALL)	EACH	7.00		
202-02.21	REMOVAL OF STORM PIPE (< 24")	L.F.	240.00		
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, DRIVEWAY, ETC.	S.Y.	40.00		
202-03.01	REMOVAL OF ASPHALT PAVEMENT	SY	200.00		
202-08.10	REMOVAL OF CURB (CONCRETE EXTRUDED MOUNTABLE & CONCRETE POST CURB)	L.F.	50.00		

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	950.00		
203-04	PLACING AND SPREADING TOPSOIL (6") (INCLUDES STRIPPING & STOCKPILING)	C.Y.	200.00		
209-05	SEDIMENT REMOVAL	C.Y.	10.00		
209-40.30	CATCH BASIN PROTECTION (FILTER SOCK PER DETAIL)	EACH	6.00		
303-01	MINERAL AGGREGATE TYPE A BASE, GRADING D	TON	600.00		
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	TON	210.00		
402-01	BITUMINIOUS MATERIAL FOR PRIME COAT (PC)	TON	3.00		
402-02	AGGREGATE FOR COVER MATERIAL	TON	14.00		
403-01 TTT1	BITUMINIOUS MATERIAL FOR TACK COAT (TC) (TTT-1)	TON	1.00		
407-20.05	SAW CUTTING ASPHALT PAVEMENT	L.F.	700.00		
411-01.11	ACS MIX (PG64-22) GRADING E ROADWAY	TON	150.00		
415-01.02	COLD PLANING BITUMINIOUS PAVEMENT	S.Y.	460.00		
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH) (0-8")	L.F.	48.00		
604-15.01	PORTLAND CEMENT GROUT	C.Y.	10.00		
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III) (TO INCLUDE COST OF EXCAVATION, PIPE, & BACKFILL) <b>SEE NOTE 2</b>	L.F.	36.00		

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III) (TO INCLUDE COST OF EXCAVATION, PIPE, & BACKFILL) <b>SEE NOTE 2</b>	L.F.	558.00		
607-46.07	CONNECT EXISTING DRAIN LINES TO STORMWATER SYSTEM	EACH	4.00		
611-07.01	CLASS A CONCRETE (PIPE ENDWALL) (0 C.Y. - 3 C.Y.)	C.Y.	1.00		
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALL)	LB.	50.00		
701-01.01	CONCRETE SIDEWALK (4") (TO INCLUDE 4" STONE BASE)	S.F.	280.00		
702-01.01	EXTRUDED MOUNTABLE CURB (ST-203) (MATCH EXISTING) (COMPLETE)	L.F.	50.00		
709-05.13	MACHINED RIP-RAP (SURGE STONE)	TON	363		
712-01.01	TRAFFIC CONTROL SEE <b>NOTE 3</b>	EACH	1.00		
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	L.F.	45.00		
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.F.	780.00		
716-05.12	PAINTED PAVEMENT MARKING (4" DETAIL WORK - ISLAND MARKING, HC AISLE)	L.F.	326.00		
716-06.03	PAINTED WORD PAVEMENT MARKING (12" NO PARKING)	EACH	3.00		
740-10.01	GEOTEXTILE (TYPE I) (SUBSURFACE DRAINAGE)	S.Y.	312		

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL
740-11.03	TEMPORARY SEDIMENT TUBE (8")	L.F.	25.00		
801-01.03	SEEDING (WITH MULCH)	S.Y.	2000.00		
805-12.01	EROSION CONTROL BLANKET (TYPE I)	S.Y.	2000.00		
SP-1	PRE-CAST YARD INLET (PER DETAIL)	EACH	5.00		
SP-2	PRE-CAST YARD INLET TOP SLAB OVER EXISTING	EACH	1.00		
SP-3	24" HDPE PIPE (TO INCLUDE COST OF EXCAVATION, PIPE, & BACKFILL) <b>SEE NOTE 2</b>	L.F.	48.00		
SP-4	REMOVE AND REPLACE ASPHALT SPEED HUMP (TO INCLUDE THERMOPLASTIC STRIPING PER DETAIL)	EACH	1.00		
SP-5	PROVIDE AND INSTALL NEW CONCRETE WHEEL STOPS WITH PINS	EA	30.00		
SP-6	REMOVE, STORE, AND RESET EXISTING U-CHANNEL POST AND SIGNS	EACH	2.00		
SP-7	OWNER'S ALLOWANCE/CONTINGENCY	L.S.	1.00	\$40,000.00	\$40,000.00

**NOTES**

(1) ITEM 105-01.01 "CONSTRUCTION STAKE, LINE, AND GRADE" SHALL ALSO INCLUDE THE SUBMITTAL OF AS-BUILT DRAWINGS, SEALED BY A LICENSED SURVEYOR IN ADOBE (PDF) FORMAT AND A DRAWING FILE IN AUTOCAD (DWG), VERSION 2013 (OR EARLIER) FORMAT.

(2) PER TDOT SPECIFICATIONS INCLUDES COST OF EXCAVATION, PIPE, PIPE CONNECTION, AND BACKFILL

(3) ITEM 712-01.01 "BASELINE TRAFFIC CONTROL" SHALL CONSIST OF FURNISHING, ERECTING, AND MAINTAINING ALL CONSTRUCTION WARNING SIGNS, BARRICADES, FLEXIBLE DRUM CHANNELIZING UNITS, TEMPORARY PAVEMENT MARKINGS, AND OTHER TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE PROVISIONS OF THE CURRENT EDITION OF THE M.U.T.C.D. . WHEN ITEM 712-01.01 IS USED IT ALSO SHALL BE

FULL COMPENSATION FOR PROVIDING TEMPORARY WORKZONE LIGHTING AND ALL EQUIPMENT, LABOR, AND MATERIALS, AND FOR FURNISHING FLAGGERS AND TRAFFIC CONES, AND FOR REMOVING CONFLICTING AND INCORRECT PAVEMENT MARKINGS, AS REQUIRED, UNTIL PROJECT COMPLETION.

(4) ANY WORK REQUIRED ON THE PLAN WITHOUT A SPECIFIC LINE ITEM SHOWN, SHOULD BE INCLUDED IN THE COST OF OTHER ITEMS.

**BASE BID TOTAL: \$** \_\_\_\_\_

The undersigned Bidder further agrees, if awarded the Contract in accordance with the Proposal, to begin work as directed upon receipt of the "Notice to Proceed" and to complete the work under the provisions of the Contract within **sixty-nine (69) consecutive calendar days** or pay as liquidated damages the sum of **\$1,000.00** per calendar day thereafter.

**The undersigned Bidder hereby certifies that he has received, read, and executed the following numbered addenda: \_\_\_\_\_, \_\_\_\_\_, \_\_\_\_\_.**

By \_\_\_\_\_  
Name Title Date

Company: \_\_\_\_\_

State Incorporation: \_\_\_\_\_

Mailing Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Telephone Number: \_\_\_\_\_

Email Address: \_\_\_\_\_

Contractor's License Number: \_\_\_\_\_

Date of Expiration: \_\_\_\_\_

**THIS PAGE LEFT BLANK INTENTIONALLY**