

# RCR&A

## RICHARD C. RINKS & ASSOCIATES, INC.

Engineers - Building Enclosure Consultants - Architects

Certified EIFS Inspection - Certified Moisture Analysis

ASCE - NSPE - TSPE - AIA - IIBEC - EDI

30 North Jefferson Avenue - P.O. Box 691 - Cookeville, Tennessee 38503-0691

Telephone 931-528-5543 Rinks-Consulting.com Facsimile 931-528-5544

### ADDENDUM 1

#### ROOF REPLACEMENT PORTION OF THREE SCHOOLS (RFB #1233) WILLIAMSON COUNTY SCHOOLS (WCS) MARCH 25, 2021

1. Minutes from Pre-Bid Meeting dated March 16, 2021 are hereby made a part of the Contract Documents.
2. Refer to Section 07550 Part 2 Products Paragraph B Item 6 in Specifications: Ridge vent for Add Alternate 1 shall be Metal Era Hi-Perf Ridge Vent or approved equal. Manufacturer shall size vent and opening in deck per NFA shown on Plans.
3. Refer to Sheet R4 and Elevations 4 and 6 on Sheet G2: Install EPDM on wall behind curved ductwork in lieu of metal panels. Remove and properly reinstall existing curved ductwork as required. Metal panels shall run from top of wall to top of ductwork similar to Elevation 6. Continue EPDM 12" behind metal panels in all locations rather than 6" shown on Plans.
4. WCS does not have a preferred Mechanical vendor. Tennessee Elite currently has their maintenance contract.
5. Contractor shall acknowledge receipt of this addendum on Bid Form.

END OF ADDENDUM

wcs-21\addendum1.doc

