

ADDENDUM 1

To: Prospective Bidders
From: Collier Engineering
Subject: WCS- RFB #1338 Tennis Court Rehab and Resurface (IHS, CHS, HEMS)
Date: February 7, 2024

This addendum shall be a part of the plans, bid book, and contract to the same extent as though it were originally included therein, and it shall supersede anything contained in the plans, bid book, and contract with which it might conflict. This addendum, including all attachments, shall become part of the contract documents. Acknowledgement of receipt of this addendum must be noted in the appropriate section of the bid form and included in the bid book/contract. Failure of any Bidder to receive this addendum shall not relieve such Bidder from any obligation under his bid as submitted.

A. Modifications to Bid Book/Contract Documents

1. Section 014 Bid Form is hereby revised to reflect the following changes:
 - a. A copy and paste error is located under the Base Bid “Centennial High School Tennis Courts: Six tennis courts” scope of work. The narrative mistakenly refers to this site as having 4 courts in the scope of work. For clarification, the Centennial HS site has 6 tennis courts.
 - b. At the pre-bid it was discovered that Pickleball lines (duct tape, not paint) have been installed to all 6 of the tennis courts (1 Pickleball court per 1 tennis court for a total of 6). We are adding to the scope of work to remove the duct tape from each of the courts (6) at Centennial HS as part of the cleaning process. WCS does not wish for Pickleball lines (taped nor painted) to be installed after resurfacing.
 - c. A revised copy of Section 14 Bid Form page 25 is attached hereto. Replace the attached page 25 and remove the original page 25.

Questions submitted to date by prospective bidders and answers from engineer:

1. **Q:** Can we work on Sunday?

A: Yes. But you must notify Collier at least 24 hours in advance for any construction work to be conducted outside of standard business hours/days.

2. **Q:** On each court at Centennial High School, Pickleball lines are taped (6 total). Does WCS want to remove existing Pickleball lines (tape not paint) and replace them with painted Pickleball lines.

A: This question is addressed in A. Modifications to Bid Book/Contract Documents letter b.

Attachments

A. Bid Book

1. Section 014 Bid Form page 25

End of Addendum 1

Centennial High School Tennis Courts: Six tennis courts

Bidder agrees to complete all site construction tasks for the Centennial High School Tennis Courts (6 courts) as listed and described in this RFB , construction documents, and specifications to include but not limited to:

Remove and store existing nets, center straps, and benches. Thoroughly clean the court surfaces, de-grass edges, remove duct taped Pickleball lines, level, and repair low spots/depressions (bird baths). Treat the existing cracks. Squeegee apply one coat of acrylic resurfacer on six court battery (±4,654sy). Squeegee apply two coats of acrylic color on six-court battery (±4,654sy). Apply two coats of acrylic to asphalt apron outside of fence lines. Court colors to be the following: Court playing area-GREEN; sideline/baseline, and overruns-RED. Remove and replace damaged line posts. Remove and repair windscreens. Layout standard 78’ tennis court lines for each of the four courts. Lines to be 2” wide, apply two coats of textured white line paint. Apply one coat of Line Prime before applying line paint. Re-paint twelve (12) existing net posts using acrylic paint. Post color to be GREEN. Install six new tennis nets with center strap. General clean-up and replacing existing site furnishings (benches and trash cans).

Centennial High School Total:

(\$ _____)

*Enter dollar amount in both words and figures.

Hillsboro Elementary/Middle School: Two-court battery

Bidder agrees to complete all site construction tasks for the Hillsboro School Tennis Courts as listed and described in this RFB , construction documents, and specifications to include but not limited to:

Mobilization, erosion and sediment control as required, traffic and pedestrian control as needed. Remove and safely store existing site furnishings (benches). Demolition, removal, and disposal of existing asphalt tennis court, concrete sidewalk, and associated items off site. Earthwork, stormwater drainage, subgrade and stone grade proof rolls, excavation, stone, asphalt, concrete sidewalk, pads, and curbing installation. Two asphalt tennis courts with color systems with playing lines. New concrete net post foundations, sleeves, posts, nets with center straps, concrete center anchors, and associated equipment for tennis courts. Black vinyl coated fencing, gates and court signage. General clean-up with landscaping and replacing existing site furnishings (benches and trash cans).

Hillsboro Elementary/Middle School Total:

(\$ _____)

*Enter dollar amounts in both words and figures.

Owner’s Allowance/Contingency: \$36,000.00